BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT37093

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/11/2019-20, Date: 11.07.2019

Name of Work:Resurve Fund to Emergency Works like water supply Desilting of drains shoulders drains maintenance of Culvets drains etc at Hegadenagara Sarrounding area Ward No 06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N LOKANATHREDDY ( )	
				In Figures	In Words
1	45.36	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 143/ Item No. 19.1/ PWD SR 2018-19	Cum	100.0	Rupees One Hundred Only
2	5.83	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 13/ Item No. 4.3/ PWD SR 2018-19	Cum	5000.0	Rupees Five Thousand Only
3	19.44	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 25/ Item No. 5.9/ PWD SR 2018-19	Sqm	5000.0	Rupees Five Thousand Only
4	4.86	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2018-19	cum	5000.0	Rupees Five Thousand Only
5	32.4	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 115/ Item No. 15.1/ PWD SR 2018-19	Sqm	200.0	Rupees Two Hundred Only
6	32.4	Providing precast slab of 250mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge- Data rate	Sqm	5000.0	Rupees Five Thousand Only
7	60	1031 - Hire Charges of J.C.B Excavator including Operator and Fuel (P. XLVIII / I. 23) PWD SR 2018-19	Day	4000.0	Rupees Four Thousand Only
8	100	1024 - Hire Charges of Tractor 50 HP including Operator and Fuel (P. XLVIII/I. 20) PWD SR 2018-19	Day	2000.0	Rupees Two Thousand Only
9	750	Engaging Causal Labours (Unskilled mazdoor Heavy) (PWD SR 2018-19 Page No. LVI/SL NO. 5)	Nos	400.0	Rupees Four Hundred Only

N, L Reddy

16/09

16/09

	Approved Qty.	Description	Unit	Approved Tender Rates of N LOKANATHREDDY ( )	
				In Figures	In Words
10	36	Providing precast slab of 100 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge- Data rate	Sqm	2000.0	Rupees Two Thousand Only
11	45.36	KSRRB M100-2. Loading and Unloading of stone boulders by manual means complete as per specification MORTH-100/chapter-1 Page No. 136/ Item No. 17.1/ PWD SR 2018-19	Cum	60.0	Rupees Sixty Only

N.L Reddy
Signature of the Contractor

Executive Engineer 16/09
Byarayanapura Division
BBMP, Bangalore - 92

16/09